SUBMITTED PROPOSALS & COSTS
Date of Bid: September 17, 2009 2:00 pm
Client: Sarpy County, Nebraska
Project: Sarpy Co. San. Landfill Phs. V Cap
TD^2 File No.: 229-223

Lessard Contracting Inc.
P.O. Box 705
Sergeant Bluff, IA 51054

ITEM	DESCRIPTION	QUANTITY	UNITS	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
1	Install and Maintain Construction Entrance	1	EA.	$2,500.00	$2,500.00								
2	Construct and Maintain Diversion Berm	350	L.F.	$5.25	$1,837.50								
3	Silt Fence, in place	1,100	L.F.	$2.10	$2,310.00								
4	Clear and Grubbing	1	LS	$15,000.00	$15,000.00								
5	Stripping	5,650	C.Y.	$1.30	$7,345.00								
6	Remove 6" PVC Drain Line w/Fittings and Concrete Outlet Collar	58	L.F.	$50.00	$2,900.00								
7	Remove Bollard	1	EA.	$150.00	$150.00								
8	Intermediate Cover Grading w/Patrol	1	LS	$14,500.00	$14,500.00								
9	Excavate and Recompact Soil Materials	30,000	C.Y.	$4.00	$120,000.00								
10	Furnish and Install Non-Woven Geotextile Gas Transmission Layer	110,350	S.F.	$0.22	$24,277.00								
11	Furnish and Install 40 Mil Geomembrane	106,650	S.F.	$0.62	$66,123.00								
12	Furnish and install Drainage Net - Bonded Geotextile	110,250	S.F.	$0.585	$64,496.25								
13	Furnish and Install 6" Perforated ABS Pipe w/Fittings, per detail	555	L.F.	$14.00	$7,770.00								
14	Furnish and Install 6" PVC Drain Line w/Fittings and Concrete Outlet Collar	107	L.F.	$42.00	$4,494.00								
15	Install 8" x 8" x 8' Metal Pipe Bollard	1	EA.	$690.00	$690.00								
16	Furnish and Install Type B Riprap over Geotextile Fabric	7	TON	$58.00	$406.00								
17	Adjust Leachate System Vent Pipes to New Grade	2	EA.	$1,510.00	$3,020.00								
18	Remove and Salvage Litter Control Chain Link Fence	705	L.F.	$2.00	$1,410.00								

No estimate published Bond: 5% of Bid

THOMPSON, DREESSEN & DORNER, INC. 10836 Old Mill Road, Omaha, NE 68154

SUBMITTED PROPOSALS & COSTS
Date of Bid: Sept. 17, 2009 2:00 pm
Client: Sarpy County, Nebraska
Project: Sarpy Co Landfill Phase V Cap
TD^2 File No.: 229-233

Lessard Contracting Inc.
P.O. Box 705
Sergeant Bluff, IA 51054

ITEM	DESCRIPTION	QUANTITY	UNITS	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
19	Remove and Dispose of Litter Control Chain Link Fence, Salvage Posts	600	L.F.	$2.00	$1,200.00								
20	Install Salvaged Litter Control Chain Link Fence	800	L.F.	$5.75	$4,600.00								
21	Erosion Control Blanket C125, in place	50	S.Y.	$2.50	$125.00								
22	Spread & Disk in Compost Material provided by Sarpy County	1,090	C.Y.	$6.50	$7,085.00								
23	Seed & Mulch Final Cover Surface and Disturbed Areas	7	AC.	$750.00	$5,250.00								
	TOTAL BID				$357,488.75 *								
	* Corrected in accordance with Notice to Bidders												

No estimate published Bond: 5% of Bid

THOMPSON, DREESSEN & DORNER, INC. 10836 Old Mill Road, Omaha, NE 68154